

7. ITEMS OF WORK AND CONSTRUCTION DETAILS

Items of work to be performed in conformance with this specification and the construction details therefor are:

A. **Bid Item 2; Clearing and Grubbing**

- (1) This item consists of all clearing and grubbing within the construction limits as shown on the drawings. Only those trees, brush and debris interfering with installation and operation of the project, as determined by the Engineer, shall be removed.
- (2) Cleared refuse can be disposed of by burning, chipping, off-site disposal or and combination thereof. Any stumps or unburned material shall be buried with a minimum of two feet (2') of cover.
- (3) In Section 6, Measurement and Payment, Method 4 shall apply.